

Embassy of India

Kathmandu

TENDER NOTICE

Sealed tender documents/quotations are invited directly from reputed and experienced bidders for **“Painting of external walls around the building of India House”** in connection with the Republic Day celebrations 2019, within Embassy premises. The last date of receipt of offer in sealed envelope is on or before **14th January, 2019 up to 1700 hrs.** Entire details of scope of work for tender documents are available on website www.indianembassy.org.np and www.eprocure.gov.in. Details can also be collected from SS (Admn, Estt & Project),/Attaché (Estt & project) Tel 01-4434276 Ext. 4179/4238.

The Embassy of India reserves the right to reject/cancel any or all bids without assigning any reason.

Kat/Adm/872/5/2013

Sd/-

(Head of Chancery)

Scope of work

Name of work: Painting of external walls around the building of India House in connection with the Republic day celebrations 2019 within Embassy premises.

Sl.No	Particulars	Quantity	Unit
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to the scratches etc. complete	2950 sq.M	Sq.M.
2	Distemping with oil bound washable distemper of approved brand and manufacturing to give an even shade : 2.1: Old works (Two or more coats)	705 sq.M	Sq.M.
3	Finishing walls with acrylic smooth exterior paint of required shade : 3.1: Old work (Two or more coat applied at 1.67 liter / 10 square meters) on existing cement paint surface	2250 sq.M	Sq.M
4	Painting with synthetic Enamel paint of approved brand and manufacture of required color to give an even shade: 4.1: One or more coats on old work	400 sq meter	Sq.M
5	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete	450 sq meter	Squar e meter

No: Kat/Admn/872/5/2013
Embassy of India
Kathmandu

Sub: Painting of external walls around the building of India House in connection with the Republic celebrations 2019, within Embassy premises.

Terms & conditions:

1. The work shall be completed within one month from the date of award of the work.
2. 3% Penalty will be recovered from the bill for delay in every 30 days.
3. Only approved quality of paint should be used for the proposed work (Asian Paints, Berger Paint or ICI paints).
4. The work shall be carried out strictly as per the latest CPWD specifications along with the updated correction slips issued by the CPWD from time to time.
5. Contractor shall make own arrangements for ladder, rope, brush and other safety measures. The rate includes all heights and all floors. Nothing shall be paid extra.
6. It is advised to make a site visit and assess the requirements before submitting Bids.
7. Important dates relating to the tender are as follows:

S. No	Particulars	Date
a	Document submission- start date	03.01.2019 (1630 hrs)
b	Document submission – last date	14.01.2019 (1700 hrs)
c	Bids opening date	15.01.2019 (1100 hrs)

8. Certificate that company/contractor pays VAT regularly and their VAT dues are cleared (*Documentary proof should be attached*)

Declaration by the Firm/Agency

This is to certify that I/we before signing this tender have read and fully understood all the terms and conditions contained herein and undertake myself/ourselves to abide by them.

(Signature of Firm with seal)

Name:

Seal:

Address:

Date:

Phone No. (O):

Schedule of Quantities

Name of work: Painting of external walls around the building of India House in connection with the Republic day celebrations 2019 within Embassy premises.

Sl.No	Particulars	Quantity	Unit	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to the scratches etc. complete	2950 sq.M	Sq.M.	
2	Distemping with oil bound washable distemper of approved brand and manufacturing to give an even shade : 2.1: Old works (Two or more coats)	705 sq.M	Sq.M.	
3	Finishing walls with acrylic smooth exterior paint of required shade : 3.1: Old work (Two or more coat applied at 1.67 liter / 10 square meters) on existing cement paint surface	2250 sq.M	Sq.M	
4	Painting with synthetic Enamel paint of approved brand and manufacture of required color to give an even shade: 4.1: One or more coats on old work	400 sq meter	Sq.M	
5	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete	450 sq meter	Sq.M	
	TOTAL			
	VAT			
	Grand TOTAL			