

**Embassy of India
Kathmandu**

Providing pressed clay tiles over PIC wing flat roof and Gutter surfaces to arrest the leakages within Embassy premises.

Scope of work

| S.No. | Description of Work | Quantity | Rate | Unit | Amount |
|--------------|---|-----------------|-------------|-------------|---------------|
| 1. | Dismantling tile work in floors and roofs laid in cement Mortar including stacking materials within 50 meters lead | | | | |
| 1.1 | For thickness of tile 25 mm to 40 mm | 10 | | Sq.meter | |
| 2 | Providing and laying pressed clay tiles (as per approved pattern 20 mm thickness of approved size) on roofs jointed with cement mortar 1:4 (One cement: Four coarse sand) mixed with 2% integral water proofing compound laid over a bed of 20 mm thick cement mortar 1:4 (One cement: Four coarse sand) and finishing neat complete | 65 | | Sq.meter | |
| 3 | Providing gola 75x75 mm in cement concrete 1:2:4 (one cement: two coarse sand: four stone aggregate 10 mm nominal size) including finishing with cement mortar 1:3 (one cement:three fine sand) as per standard design | | | | |
| 3.1 | In 75 x 75 mm deep chase | 68 | | meter | |
| 4 | Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (one cement:2 coarse sand:4 graded stone aggregate of 20 mm nominal size) over PVC sheet 1m x 1 m x 400 micron finished with 12 mm cement plaster 1:3 (One | 4 | | Each | |

| | | | | | |
|------------------|---|----|--|----------|--|
| | cement:3 coarse sand) and a coat of neat cement , rounding the edge and making and finishing the outlet all complete | | | | |
| 5 | Grading roof for water proofing treatment with | | | | |
| 5.1 | Cement concrete 1:2:4 (1cement:2coarse sand:4 graded stone aggregate 20 mm nominal size) | 10 | | cu.meter | |
| 6 | Disposal of building rubbish/malba/similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved Municipal dumping ground or as approved by Engineer-in-charge, beyond 20 kilo meter lead for all leads including all lifts involved | 5 | | cu.meter | |
| Sub-Total | | | | | |
| VAT (13%) | | | | | |
| Total | | | | | |

Embassy of India

Kathmandu

TENDER NOTICE

Sealed tender documents/quotations are invited directly from reputed and experienced bidders for Providing Pressed Clay Tiles over PIC Wing flat roof and Gutter surface to arrest the leakages within Embassy premises. The last date of receipt of offer in sealed envelope is on or before – 26th February, 2019 up to 1700 hrs. Entire details of scope of work for tender documents are available on website www.indianembassy.org.np and www.eprocure.gov.in. These documents can also be collected from Attaché (Estt & Project) Tel 01-4434276 Ext. 4179/4280

Kat/Adm/872/4/2013

Sd/-

(Head of Chancery)

**Embassy of India
Kathmandu**

Terms and Conditions

1. The contract would be for a period of 30 days.
2. Only best quality and approved materials should be used for the proposed work.
3. The agency shall make its own transportation arrangements for all the materials required at the site and disposal of any waste material.
4. The workers engaged by the agency will be the employees of the agency and the Embassy will not, in any way, be responsible for any liability/compensation on account of accident, injury or death of workers while performing their work inside the Embassy premises.
5. The agency should provide information on personnel who will be deployed in the Embassy, along with their Security Clearance (If required by the Embassy).
6. The agency shall fully equip its employees for their own expenses.
7. Payment of an item will be processed upon submission of VAT bill and cheque for the respective amount will be released to the agency.
8. The Embassy reserves the right to cancel the contract anytime with the agency.