

**Embassy of India
Kathmandu
TENDER NOTICE**

Sealed tender documents/quotations are invited directly from reputed and experienced bidders for Construction of CGS sheet roof shed (3 Nos) over DG sets at new sub-station located near AP-3 quarters within Embassy premises.

The last date of receipt of offer in sealed envelope is on or before 25 April, 2018 up to 1700 hrs. Entire details of scope of work for tender documents are available on website www.indianembassy.org.np and www.eprocure.gov.in. These documents can also be collected from **Attaché (Estt/Proj), Tel 01-4411851**

Kat/Adm/872/4/2013

Sd/-
(Head of Chancery)

Scope of work

Item	Name of Work	Quantity	Rate	Unit	Amount	DSR	Remarks
	Name of work: Construction of 3 nos of new Shed with MS tubular pipe and CGS sheet roof over DG sets at new sub-station within Embassy premises						
1	Earth work in excavation by mechanical means (hydraulic excavator) / manual means over areas (exceeding 30 cm in depth 1.50 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposal of earth to be levelled and neatly dressed						
1.1	All kinds of soil	4		cum			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				0		
2.1	1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	6		cum			
3	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc, including cutting, hoisting, fixing in position and applying of primer coat of approved steel primer, including welding and bolted with special shaped washers etc complete.				0		
3.1	Hot finished welded type tubes	2700		kg			

4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required				0		
4.1	In gratings, frames, guard bar, ladder, railings, brackets,gates and similar works	150		kg			
5	Providing corrugated GS sheet roofing including vertical/ curved surfaces fixed with polymer coated J or L hooks, bolt and nuts 8 mm diameter with bitumen and GI limpet washers or with GI limpet washers filled with white lead, including a coat of steel primer and two coat of approved paint on over lapping of sheets complete (Up to any pitch in horizontal / vertical or curved surfaces) , excluding the cost of purlins, rafters and trusses and including cutting to size and shape where ever required				0		
5.1	0.63 mm thick with zinc coating not less than 275 gm/ sqm	150		sqm			
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade (Two or more coats on new work)	200		sqm			
	Total in NRs						
	Add VAT @ 13 %						
	Total in NRs:						

No: Kat/Admn/872/4/2013
Embassy of India
Kathmandu

Additional conditions:

Sub: Construction of CGS sheet roof shed (3 nos) over Diesel Generator set at new sub-station located near AP-3 quarters within Embassy premises

1. The work shall be completed within 30 (Thirty days) from the date of award of the work.
2. 3% Penalty will be recovered from the bill for delay in every Thirty days.
3. Only best quality of approved materials should be used for the proposed work.
4. The work shall be carried out strictly as per the latest CPWD specifications along with the updated correction slips issued by the CPWD from time to time.

The Head of Chancery
05.04.2018